

HTT Flooring - Hydrocore Timber Flooring 2 of 2 Sample - Wet Sliptest SN240424-17

29 Apr 2024




Slip Resistance Classification of New Pedestrian Surfaces - AS4586:2013

This Test Report Is In Accordance with Appendix A	Wet Pendulum Test
Date Tested:	24 Apr 2024
Test Report Number:	SN240424-17
Client Name & Billing Address:	HTT Flooring Pty Ltd - Unit 2, 8 Gunya Street Regents Park NSW 2143
Project Name or Test Location:	Sliptest Australia NSW Headquarters - 5 Joynton Ave, Zetland NSW 2017
Surface Tested :	Hydrocore Timber Flooring 2 of 2 Sample
Wet Pendulum Test carried out using :	Slider 96 (4S) Rubber slider
Any Variations to Standards	N/A
Testing Officer / Approved Signatory:	Shenea Neill
Pendulum in use - Calibration Date :	#1133 - Munro-Stanley Portable Skid Tester - (C: 13.10.23 - EN 13036-4)

Signature of Approved Signatory :

Test Results : (Samples and Test Information Supplied by Client)

Sample No.	Swing 1	Swing 2	Swing 3	Swing 4	Swing 5	Mean BPN	SCV :	Surface Picture
Blackbutt	30	29	28	27	27	27	N/A	
Fortune Cookie	39	39	38	37	37	37	N/A	

Sample No.	Swing 1	Swing 2	Swing 3	Swing 4	Swing 5	Mean BPN	SCV :	Surface Picture
Brandy	36	36	36	35	35	35	N/A	
Golden Fog	25	25	24	24	24	24	N/A	
Golden Fog	26	26	25	24	24	24	N/A	

Reported SRV For Test Area :

29

CLASSIFICATION using Slider 96 (4S Slider)

P2 = 25 - 34

Accredited for Compliance with ISO/IEC 17025. The information presented herein and on the Sliptest Report is copyright and is protected by copyright law, any reproduction of this information and test report except in full is prohibited. Sliptest Australia Pty. Ltd. performed this on site test with reference to the following Australian Standard testing criteria, of AS 4586:2013 Classification of new pedestrian surface materials. Appendix A - Wet Pendulum Test Method and Hand Book HB 198: 2014 with reference to AS/NZS 4663: 2004 Slip Resistance measurement of existing pedestrian surfaces and HB 197: 1999. These results to not account for Future Wear, Maintenance or Contamination of this surface once in-situ.

Page 1 of 1 - END OF REPORT